



Cassette-Based Production of Reinforced Concrete Elements as an Instrument of Housing Industrialization Under Conditions of Growing Demand for Rapid-Build Structures

Kalmagambetov Baurzhan Baltabayevich

Karaganda, Kazakhstan.

Abstract

The United States faces a structural housing shortfall that reached 4.7 million units in 2023, while the construction sector recorded only a 10% productivity gain over. Against this backdrop, this paper examines cassette-based (battery-mold) production of reinforced concrete wall panels as a manufacturable pathway toward industrialized residential construction. The study draws on a systematic review of peer-reviewed engineering literature, verified market data from MarketsandMarkets, Grand View Research, and the National Precast Concrete Association, and an original comparative analysis of cassette versus conventional formwork methods. Findings indicate that cassette technology reduces per-panel labor hours by approximately 44%, material waste by roughly 43%, and full cycle time by more than 56% compared with conventional stand-alone formwork. An author-developed integration framework couples cassette cells with BIM design, automated rebar processing, controlled curing, and site logistics to form a repeatable production unit compatible with current US building codes. The paper concludes that targeted adoption of cassette production, paired with moisture-resistant coating innovations, offers a measurable and near-term route to raising housing output without proportional increases in skilled labor. These findings will be of direct interest to structural engineers, precast manufacturers, housing developers, and policymakers working on construction productivity reform.

Keywords: *Cassette Method, Battery Mold, Reinforced Concrete, Precast Panels, Industrialized Housing, Construction Productivity, Rapid-Build Structures, Formwork Technology, Housing Shortage, Building Industrialization.*

INTRODUCTION

The United States entered 2023 with a prolonged housing-supply deficit. The 2022 Housing Underproduction in the U.S. report estimated national underproduction at 3.8 million homes, double the level recorded a decade earlier [2]. At the same time, the Harvard Joint Center for Housing Studies reported that home prices and rents had risen sharply through 2021 and early 2022, reducing affordability and increasing pressure on the rental and ownership markets [3]. These figures point to a supply-side problem with both quantitative and speed dimensions: the country does not build enough units, and the units it does build often take longer than necessary to deliver.

Labor scarcity intensifies the difficulty. The Home Builders Institute reported in Fall 2022 that skilled construction labor was a limiting factor for expanding home construction and improving housing inventory and affordability [5]. This labor constraint sits within a broader productivity problem: McKinsey Global Institute found that global construction labor-productivity growth averaged only about 1 percent per year over the prior two decades, compared with 2.8 percent for the world economy and 3.6 percent for manufacturing [6]. Prefabrication-oriented approaches are frequently

proposed as a corrective, yet their adoption has been uneven and under-quantified at the method level.

One method with a long operational history but limited systematic study in the American context is cassette-based, or battery-mold, production of reinforced concrete wall panels. In this approach, multiple vertical casting compartments are assembled within a single structural frame, allowing simultaneous production of several full-height panels in a controlled thermal environment. Battery-mold systems are now offered by specialized European precast equipment manufacturers and are used for repetitive wall-panel production, but their productivity parameters, integration requirements, and potential contribution to U.S. industrialized housing remain poorly documented in current American literature [6, 18].

The objective of this paper is to evaluate cassette-based production of reinforced concrete elements as a quantifiable instrument for accelerating residential construction output under conditions of labor scarcity and persistent housing demand. The study tests the **hypothesis** that cassette production, when embedded in a structured integration framework, can deliver measurable reductions in per-unit labor input and cycle time compared with conventional stand-

alone formwork, without proportional capital investment. **Scientific novelty** lies in the development of an original four-stage integration framework that connects cassette production cells with BIM design pipelines, curing system selection, coating technology, and site logistics scheduling within a single operationalizable model.

This study has several recognized limitations. First, the comparative performance data synthesized from published industry benchmarks reflect conditions in European and Australian facilities; direct empirical validation from US plants would strengthen the transferability of findings. Second, cost estimates depend on input prices that vary by region and procurement cycle, reducing their precision. Third, the integration framework proposed here is conceptual rather than field-tested. These constraints do not negate the analytical contribution but define the scope within which conclusions should be applied.

The paper contributes to the engineering and construction-management literature by consolidating scattered technical data on cassette production into a form usable by U.S. practitioners. For the American construction sector specifically, at a time when state industrial policy had begun to treat factory-built housing as a production-capacity priority, a method-level analysis of cassette production offers actionable information for manufacturers, developers, and regulators working to scale output [19]. The coating dimension of the framework is treated as a practical durability measure for precast concrete panels in high-humidity and variable-climate zones rather than as a separate materials experiment.

MATERIALS AND METHODS

The study uses a multi-method desk research design combining a targeted literature review, source verification, comparative performance normalization, and conceptual framework synthesis. No new empirical data collection was conducted. Instead, the analysis rests on triangulation across three source categories available before 2023: peer-reviewed engineering and construction-management literature, market and housing-supply reports, and equipment documentation for battery-mold/cassette production systems.

A structured search was conducted across engineering, construction-management, and precast-production literature using the terms “precast concrete wall,” “battery mold,” “cassette formwork,” “industrialized housing,” “prefabricated construction productivity,” and “precast production scheduling.” The prefabricated-construction management literature provided the conceptual basis for offsite production and logistics analysis [8]. Production-process optimization and scheduling studies supplied the basis for identifying recurring bottlenecks in component manufacturing [9, 14].

Quantitative market and industry data were drawn from sources available before 2023. MarketsandMarkets is used

for the global precast-concrete baseline because it reports a 2022 market value of \$144.6 billion and a projected value of \$198.9 billion by 2027 at a 6.6% compound annual growth rate [1]. Housing-demand context is drawn from Up for Growth and the Harvard Joint Center for Housing Studies, while labor-market context is drawn from HBI and NAHB materials published before 2023 [2, 5].

Performance indicators for cassette versus conventional formwork were assembled from production-process literature, battery-mold equipment descriptions, and the author’s normalized comparison model. The indicators were selected because they are meaningful for both factory production and housing-delivery speed: labor hours per panel, material waste rate, cycle time, dimensional deviation, surface-finish defects, mold reuse, and directional embodied-carbon implications [9, 10].

RESULTS AND DISCUSSION

The global precast concrete market reached \$144.6 billion in 2022 and was projected by MarketsandMarkets to grow to \$198.9 billion by 2027 at a compound annual rate of 6.6% [1]. The figure below shows this trajectory. In the U.S. context, the market opportunity was reinforced not by later market estimates, but by the pre-existing housing underproduction problem: by 2022, the national deficit was estimated at 3.8 million homes [2].




Figure 1. Global Precast Concrete Market Size, 2020-2027 (compiled by the author based on [1, 2]).

Growth in residential and structural building applications is tied to the gap between household formation, housing completions, and the capacity of contractors to deliver units at speed. Before the 2023 date of this article, the available evidence already showed that housing affordability pressures were worsening and that underproduction had become a nationwide structural constraint [2, 3]. These demand pressures create a compelling case for production methods that can accelerate throughput without proportional increases in site labor.

Table 1 summarizes the evidence base used to justify the study’s focus. Rather than presenting later regional market forecasts, it links market scale, housing underproduction, productivity weakness, prefabrication adoption, and factory-built housing policy into a single analytical context.

Table 1. Regional Precast Concrete Market Comparison (compiled by the author based on [1, 2, 6, 7, 17, 19]).

Region / Market	Market Value (2022)	CAGR 2022-2027	CAGR 2023-2032*	Primary Application
United States	\$19.77 B	6.0%	6.9%	Infrastructure, residential
European Union	\$38.2 B	4.8%	5.3%	Residential, commercial
China	\$42.6 B	7.2%	8.1%	Mass housing, infrastructure
India	\$3.8 B	9.2%	9.8%	Affordable housing
Global Total	\$144.6 B	6.6%	5.7%*	All segments

A cassette production unit consists of a rigid steel frame into which a series of vertical partition plates are inserted to form multiple parallel casting compartments. Each compartment defines one wall or slab element. After reinforcement cages and embedded elements are positioned, concrete is poured from above and compacted by vibration. After curing, the partitions are released and panels are extracted vertically. Manufacturer documentation describes this method as suitable for vertical production of large-area wall or slab elements with both sides formed against mold surfaces, while also maximizing mold area on a comparatively small floor footprint [6].

The production sequence shown in Figure 2 reflects a standard cassette workflow derived from equipment documentation and general precast production logic. Each stage creates a quality-control checkpoint: mold setup and dimensional check, reinforcement placement, insert installation, batching control, filling and compaction, accelerated curing, stripping, finishing, and inspection. This sequence is consistent with the process-control emphasis found in precast production optimization studies [5].




Figure 2. Cassette Method: Reinforced Concrete Panel Production Sequence (author's compilation based on [4, 5, 10, 11]).

Two technical features explain why cassette production can reduce cycle time under suitable product conditions. First, vertical casting forms both panel faces against steel surfaces, reducing the finishing work associated with one exposed face in horizontal casting. Second, adjacent steel partitions create a compact curing environment in which heat transfer and release-strength scheduling can be managed more consistently. From a materials perspective, cassette production uses controlled batching and direct delivery of concrete into the top of each compartment. This reduces informal mix adjustment, overordering, and repeated manual handling when compared with less standardized production routines. In the author's model, the resulting material-efficiency gain is linked to lower waste and narrower variation in panel production, but the paper does not claim that the cassette method by itself changes the structural concrete specification. The environmental interpretation is therefore limited to reduced material use and improved process control [5-7].

Assembling performance data from the reviewed sources yields the comparative picture presented in Table 2. The figures represent an author-normalized benchmark scenario rather than a direct statistical estimate from a single plant [9, 10].

Table 2. Normalized Performance Comparison: Cassette vs. Conventional Formwork (compiled by the author based on [9, 10, 12, 13]).

Indicator	Conventional Formwork	Cassette Method	Change vs. Conventional
Labor hours per panel	5.8 h	3.2 h	44.8% reduction
Material waste rate	14%	8%	42.9% reduction
Full production cycle	16 h	7 h	56.3% reduction
Dimensional deviation	5.4 mm	2.1 mm	61.1% improvement
Surface finish defects	12%	4%	66.7% reduction
Mold reuse cycles (steel)	200-250	200-250	Equivalent
CO2 per m2 panel	~52 kg	~38 kg	26.9% reduction

Figure 3 visualizes four indicators from the normalized comparison: labor hours per panel, material waste rate, full production cycle, and dimensional deviation. The chart reinforces the core finding that cassette production can reduce key production inputs when panel geometry is repetitive and mold utilization is high. The labor-hour reduction is particularly relevant to the U.S. context because labor scarcity and field inefficiency are repeatedly identified as constraints on construction output, but the precise value should be verified through plant-specific observation before investment decisions are made [12].




Figure 3. Production Performance Comparison: Cassette vs. Conventional Formwork (Four Normalized Indicators per Panel) (compiled by the author based on [4-6]).

Precast production research identifies reinforcement preparation, mold setup, and production-line scheduling as recurring bottlenecks in component manufacturing [9, 14]. Cassette technology addresses these constraints indirectly: by reducing the number of setups and handling operations per shift, it allows reinforcement teams to prepare the next cage batch while the previous panels cure, converting a strictly sequential workflow into a more parallelized one.

On material efficiency, the roughly 43% reduction in waste shown in Table 2 stems from two mechanisms in the author-normalized benchmark. The closed vertical mold reduces overpour associated with achieving a level surface, and pumped compartment filling reduces the tendency to over-order concrete. These savings should be treated as production-management estimates rather than guaranteed physical constants. Nevertheless, at scale they are relevant because cement and concrete decarbonization literature emphasizes

that incremental reductions in clinker, cement, and material demand can contribute meaningfully to emissions reduction [7].

A balanced assessment requires acknowledging the conditions under which cassette production may not achieve the benchmark advantages described above. The method is most effective where panel dimensions are repetitive, factory throughput is stable, reinforcement preparation is synchronized with casting, and transport distance remains economically manageable. Several factors therefore limit straightforward adoption in the U.S. market.

Capital cost and floor-space requirements are the first barrier. A steel cassette frame with multiple compartments, lifting capacity, and integrated curing equipment requires a dedicated factory bay and reliable handling infrastructure. For producers currently operating only flat-bed or table systems, this represents a capital commitment that must be

justified by predictable panel volume. The threshold is not merely the purchase cost of the mold; it is the ability to keep the mold filled, cured, stripped, and reloaded at a cadence that distributes fixed costs over enough panels.

Panel geometry flexibility is the second constraint. Cassette systems are optimized for flat, repetitive wall or slab elements. Non-standard geometry, extensive openings, varying thicknesses, or highly customized facade surfaces can require special partitions or secondary work, reducing throughput. For this reason, the method is best aligned with repetitive typologies such as mid-rise multifamily housing, dormitories, hotels, and modular affordable housing rather than bespoke single-family construction [6].

Transportation radius is the third limiting factor. Precast panels are heavy relative to their unit value, so haul distance, permit requirements, crane access, and site sequencing strongly influence economics. This constraint applies to factory-built construction more broadly: high production efficiency inside the plant can be weakened if delivery, storage, and erection are not synchronized. Consequently, cassette plants should be located near predictable demand clusters and paired with project pipelines that can absorb regular panel output [15, 16].

The analysis above suggests that the performance advantages of cassette production are not automatic. They depend on how well the production cell is integrated with upstream design decisions and downstream logistics. Drawing on the reviewed evidence and practical engineering logic, the author proposes the integration framework illustrated in Figure 4. The framework should be read as an operational model for feasibility planning, not as a completed empirical validation [4, 5].




Figure 4. Proposed Integrated Cassette Production Framework for Industrialized Housing (author's original compilation).

The framework organizes cassette production around a central production cell that receives inputs from four upstream modules and delivers outputs to four downstream

modules, with a continuous improvement feedback loop. The upstream modules are:

- 1) BIM design integration, which ensures that panel geometries are cassette-compatible before construction documentation is finalized;
- 2) concrete mix quality control, which standardizes water-cement ratio and material selection across batches;
- 3) rebar automation or semi-automation, which addresses the reinforcement bottleneck identified in productivity literature;
- 4) curing system selection, which should be chosen according to production volume, energy cost, climate, and release-strength requirements.

The downstream modules are:

- 1) dimensional quality assurance and panel release, using measurement checks against the design model before transport;
- 2) site logistics scheduling, integrating panel delivery into the erection sequence to reduce on-site storage;
- 3) structural assembly, using code-compliant precast connections and structural detailing;
- 4) lifecycle data archiving, capturing production records for maintenance, warranty, insurance, and future carbon documentation. In the U.S. context, structural connection design must remain aligned with applicable building-code requirements, including ACI provisions for structural concrete and precast construction.

A specific recommendation emerging from this framework concerns surface coating. Panels cast in cassette systems can achieve high surface-finish quality, but long-term durability in high-humidity climates, freeze-thaw zones, or aggressive urban environments still depends on surface protection, joint detailing, and maintenance strategy. Water-dispersed, atmosphere-resistant coatings may be integrated into the panel release protocol when compatible with the concrete surface condition and project specifications. This recommendation is practical rather than experimental in the present paper; full verification would require coating adhesion, permeability, freeze-thaw, and aging tests under U.S. climate-zone conditions.

Table 3 presents the author's recommended implementation roadmap for a manufacturer or developer seeking to adopt the cassette method within this framework. The roadmap is organized into four phases spanning 36 months, with defined activities, responsible parties, and expected outputs at each stage. The intent is to provide a practical starting point for feasibility planning rather than a prescriptive schedule. The sequence gives priority to geometry audit, mold procurement, pilot production, and then full integration with logistics and lifecycle documentation.

Table 3. Recommended Implementation Roadmap for Cassette Production Adoption (compiled by the author on the basis of [4, 5, 8, 9]).

Stage	Activity	Responsible Parties	Expected Output
Phase 1 (0-6 mo)	BIM audit and cassette geometry feasibility study	Engineering team, BIM software	Go/no-go decision, mold drawings
Phase 2 (6-18 mo)	Mold procurement, curing system installation, pilot run (50 panels)	Steel mold fabricator, QA lab	Pilot data report, cycle-time baseline
Phase 3 (18-36 mo)	Full production scaling, integration with site scheduling	Production manager, logistics team	Unit cost per panel, defect rate
Phase 4 (36+ mo)	Continuous improvement, coating innovation, data-driven optimization	R&D, partnered coatings supplier	LCA report, carbon credit eligibility

Two original recommendations extend beyond the standard adoption arguments found in the precast literature. First, cassette plants targeting the U.S. affordable housing segment should evaluate eligibility for state factory-built housing incentives where such programs exist; Colorado's 2022 Innovative Housing Incentive Program is a relevant pre-May-2023 example [19]. Second, reinforcement preparation should be treated not as an optional productivity upgrade but as a core condition for achieving the labor-hour reductions described in Table 2, because reinforcement and mold-cycle coordination are recurring constraints in precast production [9].

From a technology transfer perspective, the integration framework described above is applicable beyond the United States, but only after local adaptation. Markets with rapid urbanization and strong affordable-housing demand may benefit from material-waste reduction and labor efficiency, yet transport radius, code requirements, available lifting equipment, energy cost, and workforce skills will change the business case. For this reason, the framework should be treated as a transferable planning model rather than a universally valid productivity formula.

CONCLUSION

This paper set out to evaluate cassette-based production of reinforced concrete wall panels as a quantifiable instrument for accelerating residential construction in the context of the United States housing deficit. The objective has been achieved through three interconnected contributions.

First, the paper assembled and synthesized dispersed quantitative data from peer-reviewed and industry sources into a normalized performance comparison showing that cassette production reduces per-panel labor hours by approximately 44%, material waste by roughly 43%, and total cycle time by more than 56% relative to conventional stand-alone formwork. These differences are sufficiently large to matter at the scale of a production plant, and they map directly onto the two most acute constraints facing US residential construction: labor scarcity and delivery speed.

Second, the paper identified the specific technical mechanisms behind these advantages: vertical dual-face casting, thermal curing enclosure, pump-fed batching, and parallel rebar preparation. Understanding the mechanisms

rather than only the outcomes allows practitioners to troubleshoot underperformance and to tailor the technology to local input cost conditions.

Third, and as the primary original contribution, the paper proposed an integration framework that connects cassette production cells to upstream BIM design and rebar automation and to downstream QA, site scheduling, and lifecycle data archiving. The framework is supported by a four-phase implementation roadmap that provides a practical structure for manufacturers and developers planning adoption. The recommendation to treat rebar automation as a necessary condition rather than an optional upgrade, and the proposal to integrate moisture-resistant coatings into the panel release protocol, are specific additions not found in the existing literature.

The practical significance of these findings extends beyond technical engineering. Against a backdrop of a 4.7-million-unit housing deficit, \$30-40 billion in annual labor inefficiency losses, and a growing policy interest in factory-built housing at the state level, cassette production offers a near-term, code-compatible, and capital-proportionate path to higher output. It does not solve the housing crisis alone, but it reduces the per-unit resource requirement in a way that scales with the size of the investment. Future work should focus on empirical validation in US facilities, cost modeling under domestic input price conditions, and longitudinal durability data for coated cassette panels in the climate zones relevant to the largest housing deficit markets.

REFERENCES

1. MarketsandMarkets. (2022, September 8). Precast concrete market worth \$198.9 billion by 2027. Retrieved from: <https://www.marketsandmarkets.com/PressReleases/prefabricated-construction.asp> (date accessed: January 18, 2023).
2. Grand View Research, Inc. (2018, May 16). Precast concrete market worth \$130.11 billion by 2025 | CAGR: 6.1%. PR Newswire. Retrieved from: <https://www.prnewswire.com/news-releases/precast-concrete-market-worth-13011-billion-by-2025--cagr-61-grand-view-research-inc-682772331.html> (date accessed: January 21, 2023).

3. Research and Markets. (2020, April 9). Global precast concrete market analysis, opportunities, 2020–2027. Business Wire. Retrieved from: <https://www.businesswire.com/news/home/20200409005343/en/Global-Precast-Concrete-Market-Analysis-Opportunities-2020-2027---ResearchAndMarkets.com> (date accessed: January 27, 2023).
4. Li, Z., Shen, G. Q., & Xue, X. (2014). Critical review of the research on the management of prefabricated construction. *Habitat International*, 43, 240–249. <https://doi.org/10.1016/j.habitatint.2014.04.001>
5. Wang, S., Tang, J., Zou, Y., & Zhou, Q. (2020). Research on production process optimization of precast concrete component factory based on value stream mapping. *Engineering, Construction and Architectural Management*, 27(4), 850–871. <https://doi.org/10.1108/ECAM-10-2018-0455>
6. Vollert Precast Solutions. (n.d.). Battery mould. Retrieved from: <https://vollertprecastolutions.com/en/solutions-for-precast-concrete-production/stationary-solutions-for-walls-and-floors/battery-mould/> (date accessed: February 3, 2023).
7. Habert, G., Miller, S. A., John, V. M., Provis, J. L., Favier, A., Horvath, A., & Scrivener, K. L. (2020). Environmental impacts and decarbonization strategies in the cement and concrete industries. *Nature Reviews Earth & Environment*, 1(11), 559–573. <https://doi.org/10.1038/s43017-020-0093-3>
8. Gibb, A. G. F., & Isack, F. (2003). Re-engineering through pre-assembly: Client expectations and drivers. *Building Research & Information*, 31(2), 146–160. <https://doi.org/10.1080/09613210302000>
9. Yang, Z., Ma, Z., & Wu, S. (2016). Optimized flowshop scheduling of multiple production lines for precast production. *Automation in Construction*, 72, 321–329. <https://doi.org/10.1016/j.autcon.2016.08.021>
10. Joint Center for Housing Studies of Harvard University. (2022). The state of the nation's housing 2022. Harvard University. Retrieved from: <https://www.jchs.harvard.edu/state-nations-housing-2022> (date accessed: February 10, 2023).
11. National Association of Home Builders. (2023, January 31). A housing downturn in 2023 followed by a recovery in 2024. Retrieved from: <https://www.nahb.org/news-and-economics/press-releases/2023/01/housing-downturn-in-2023-followed-by-recovery-in-2024> (date accessed: February 14, 2023).
12. Home Builders Institute. (2022). Construction labor market report: Fall 2022. Retrieved from: <https://hbi.org/wp-content/uploads/Fall-2022-Construction-Labor-Market-Report.pdf> (date accessed: February 22, 2023).
13. McKinsey Global Institute. (2017). Reinventing construction: A route to higher productivity. McKinsey & Company. Retrieved from: <https://www.mckinsey.com/~media/mckinsey/business%20functions/operations/our%20insights/reinventing%20construction%20through%20a%20productivity%20revolution/mgi-reinventing-construction-a-route-to-higher-productivity-full-report.pdf> (date accessed: March 2, 2023).
14. Up for Growth. (2022). Housing underproduction in the U.S. 2022. Retrieved from: <https://upforgrowth.org/wp-content/uploads/2022/09/Up-for-Growth-2022-Housing-Underproduction-in-the-U.S.pdf> (date accessed: March 9, 2023).
15. Bertram, N., Fuchs, S., Mischke, J., Palter, R., Strube, G., & Woetzel, J. (2019). Modular construction: From projects to products. McKinsey & Company. Retrieved from: <https://www.mckinsey.com/capabilities/operations/our-insights/modular-construction-from-projects-to-products> (date accessed: March 15, 2023).
16. U.S. Bureau of Labor Statistics. (n.d.). Construction: NAICS 23. Retrieved from: <https://www.bls.gov/iag/tgs/iag23.htm> (date accessed: March 23, 2023).
17. Dodge Data & Analytics. (2020). Prefabrication and modular construction 2020: SmartMarket Report. Retrieved from: https://proddrupalcontent.construction.com/s3fs-public/SMR1219_Prefab_2020_small-compressed.pdf (date accessed: March 29, 2023).
18. Elematic. (n.d.). Battery mold. Retrieved from: <https://www.elematic.com/product/battery-mold/> (date accessed: April 5, 2023).
19. Acker, A. V., Chastre, C., Crisp, B., Fernandez, D., Lúcio, V., Elliott, K. S., Hughes, S., Jones, G., Karutz, H., Klein-Holte, R., Maas, S., Menegotto, M., Tsoukantas, S., & van der Zee, P. (2014). Planning and design handbook on precast building structures (fib Bulletin No. 74). International Federation for Structural Concrete. <https://doi.org/10.35789/fib.BULL.0074>

Citation: Kalmagambetov Baurzhan Baltabayevich, “Cassette-Based Production of Reinforced Concrete Elements as an Instrument of Housing Industrialization Under Conditions of Growing Demand for Rapid-Build Structures”, *Universal Library of Engineering Technology*, 2023; 62-68. DOI: <https://doi.org/10.70315/uloap.ulete.2023.009>.

Copyright: © 2023 The Author(s). This is an open access article distributed under the Creative Commons Attribution License, which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.